Geosynthetic Reinforced Segmental Retaining Walls (SRWs)

- 1.0 Background and Aesthetics
- 2.0 Retaining Wall Costs
- 3.0 Design Issues and Example Problem

(|)

- 4.0 Cases of Inadequate Performance
- 5.0 Concerns
- 6.0 Summary and Conclusions

1.0 Background and Aesthetics

Historic progression of wall types:

- rigid and/or gravity walls
- bin and crib walls
- MSE metallic reinforcement

MSE – polymeric reinforcement
 This paper focuses on the last category.

Various types of wall facing:

- wrap-around
- timber
- welded-wire mesh
- gabion (metal or polymer)
- precast full-height concrete
- precast panel units (various shapes)
- modular concrete blocks, or segmental retaining walls (SRWs)









Types of polymeric* reinforcement:

Geogrids (mainly) Geotextiles (sometimes) Geostraps/Geoanchors (rarely)

*HDPE, PET & PP mainly; PA, FG occasionally



"SRWs are Hot"!

factory fabrication of blocks good quality control at a low cost modular construction in field eliminates large equipment no need for carpenters, rod-setters, etc. conforms to any line and grade good tolerance for irregularities can accommodate reasonable settlement outstanding aesthetics






















Photo 1. Segmental retaining wall (SRW) components of a completed bridge abutment.















2.0 Retaining Wall Costs

wall categories: gravity; crib/bin; MSE (metal); MSE (geosynthetics) wall heights: low (< 4.5 m); medium; high (> 9.0 m) Previous surveys: Lee (1973); VSL (1981); Yako & Christopher (1988)

The GRI Survey (1998)

contacted all 50-DOTs
obtained responses from 40 states
includes thousands of walls
these are bid prices of public financed walls

prices are in \$/m² of wall facing




Comparison of Retaining Wall Costs

Wall Category	Wall Height	Lee, et. al (1973)	VSL Corp. (1981)	Yako & Christopher (1988)	J. Koerner, et. al. (1998)
Gravity	high	300	570	570	760
	medium	190	344	344	573
	low	190	344	344	455
Crib/Bin	high	245	377	377	I/D
	medium	230	280	280	390
	low	225	183	183	272
MSE Walls	high	140	300	300	358
(metal)	medium	100	280	280	381
	low	70	172	172	341
MSE Walls	high	N/A	N/A	250	357
(geosynthetic)	medium	N/A	N/A	180	279
	low	N/A	N/A	130	223

Notes: I/D = inadequate data N/A = not available at time of survey




Gravity Walls




Æ

Crib/bin walls




Æ


MSE (metal)



MSE (Geosynthetics)



1



Statistical Data for Retaining Wall Costs from J. Koerner, et al. (1998) Survey


Wall	Wall Height	Wall Costs in dollars/sq. m		Variance
Category	(m)	Mean	Std. Dev.	(%)
Gravity walls	>9.0	760	180	24
	4.5 to 9.0	573	224	39
	< 4.5	455	166	37
Crib/bin walls	>9.0	I/D	I/D	I/D
	4.5 to 9.0	390	129	33
	< 4.5	272	98	35
MSE (metal)	>9.0	385	122	32
	4.5 to 9.0	381	126	33
	< 4.5	341	135	40
MSE	>9.0	357	73	20
(geosynthetic)	4.5 to 9.0	279	81	29
	< 4.5	223	67	30



Thus:

- MSE (GS) walls are lowest cost over all height categories
- with continued strong growth costs may be driven lower

prices for privately financed walls are lower – some (sparse) data follows



3.0 Design Issues

External Stability	Internal Stability
 mass sliding* 	 tensile overstress (spacing)*
 bearing capacity* 	 soil pullout*
 overturning 	 facing connection overstress

*dependent upon lateral earth pressure assumptions




Soil Zones in SRWs

- drainage soil (same as block infill): (gravel, typ. #57 stone)
- 2. reinforced soil:
 - (varies greatly, more later)
- 3. retained soil

(in-situ soil or local borrow)

4. foundation soil or rock:(in-situ condition or compacted fill)






Design Methods in Common Use

Item	modRankine	FHWA	NCMA
K _a – basis	Rankine	Coulomb	Coulomb
K _p – basis	neglect	neglect	neglect
earth pressure angle	horizontal	inclined	inclined
surcharge	applicable	applicable	applicable
wall batter	not applicable	applicable	applicable
inclined backslope	not applicable	applicable	applicable



Example Problem (blocks are 0.25-m high)



Results of Example Problem Illustrating Three Design Methods

(a) External Stability Consideration

Item	Modified	FHWA	NCMA
	Rankine		
FS (Foundation Sliding)	2.07	2.30	2.87
FS (Bearing Capacity)	3.59	3.59	5.35
FS (Overturning)	3.43	*	4.93

* = generally not a concern



Results of Example Problem (cont.)

(b) Internal Stability Considerations

Note: Reinforcement layer at El. -3.75 m is used for illustration

Item	Modified	FHWA	NCMA
	Rankine		
FS (tensile overstress)	2.88	2.84	2.91
FS (soil pullout)	10.90	13.80	15.40
Str. (facing connection)	n/a	14.40	12.00

n/a = not applicable

Comparison of Example Problem Results "Assuming that FHWA has it right"!

Design Issue	Mod. Rankine	FHWA	NCMA
"external stability"			
 mass sliding 	111%	100%	80%
 bearing capacity 	100	100	67
 overturning 	100	n/a	70
"internal stability"			
• tensile overstress	99%	100%	98%
 soil pullout 	123	100	85
 facing connection 	n/a	100	83

Thus: mod. Rankine = most conservative FHWA = intermediate NCMA = least conservative



4.0 Cases of Inadequate Performance

there are ~ 35,000 MSE walls with GS reinforcement eprhaps 30% (~ 10,000) are SRWs percentage of problem walls is not known but probably very low from literature and GRI files 12-serviceability cases, e.g., deformation 14-failure cases, i.e., collapse


























Root Causes in Inadequate Wall Performance

Category	Construction	Design/Spec
Serviceability (12)	5	7
Failure (14)	3	11

- 3 of the construction cases and 17 of the design/spec cases (20 of 26) had silt and/or clay backfill soils in reinforced zone
- 5 of the construction cases were due to lack of CQC and/or CQA
- 1 case was a deep shear failure, thus....
- 25 of 26 were poor backfill soil or poor quality construction and/or lack of inspection




5.0 Concerns

5.1 low permeability backfill
5.2 QC and QA
5.3 additional design issues
5.4 maintenance

5.1 – Low Permeability Backfill Soil

Sieve	Particle	Percent Passing Given Sieve		
Size	Size (mm)	Koerner	FHWA	NCMA
		(1994)	(1998)	(1997)
-	100	-	-	75-100
No. 4	4.76	100	100	20-100
No. 10	2.0	90-100	-	-
No. 40	0.42	0-60	0-60	0-60
No. 100	0.15	0-5	-	-
No. 200	0.075	0	0-15	0-35

ÐE




Diameter (mm)


Percent finer by weight

()


SRW Collapse Progression Due to Hydrostatic Pressure




(a) crack forms; water enters and pressure mobilized




(d) overlying blocks drop accordingly




(b) wall deforms; pressure continues



(e) progressively blocks drop along with gravel and some backfill soil




(c) deformation continues; single block dislodges and drop to toe of wall




Æ

(f) wall facing and gravel gone; partial MSE mass remains behind







Comments

sand backfill in reinforced zone is preferred

- gravel is acceptable, but cost may be high and RF_{ID} will also be high
- If silt and/or clay soils are used they must be drained externally and/or internally
- proper surface drainage is especially critical
- design must carefully consider the effects of hydrostatic pressures from all sources and directions

5.2 – Quality Control and Quality Assurance

- MQC is responsibility of the manufacturer
- CQC is responsibility of the <u>contractor</u>!
- where are contractor's "quality manuals"?
- what about contractors ISO 9000 and ISO 14,000?

œþ'

- QA is the responsibility of <u>owner</u>!
- should also be of concern to <u>designer</u>
- refers to both MQA and CQA (blocks & GSs)
- NICET has a QA certification program for geosynthetics inspectors.... let's use it !





























Suggested Levels of CQA* as Percentage of Construction Time

Duration \rightarrow	Temporary	Permanent		
Significance 🗼				
Noncritical	33%	67%		
Critical	67%	100%		

۲þ۱

*MQA can be by testing or via certification

5.3 – Additional Design Issues

seismic design
friction connections
details, e.g., penetrations
durability of facing (or alternate)
durability of GS reinforcement

Various Mechanical Connections


pins or combs
wrap-around bars
keepers in grooves




Mesa Block and Connector System

Verdura Block and Connector System





New Castle Wall System



On Durability of GS Reinforcement

Polymer	CEG	M_{w}	UV	OIT	Oven	ESCR
PET						
HDPE				?	?	?
PP				?	?	

 $\sqrt{}$ = AASHTO has criteria



Recommended Specifications Items to Assure Long Lifetime

(a) Polyester (AASHTO)

 Carboxyl end group < 30 via GRI-GG7
 Molecular weight > 25,000 via GRI-GG8

(b) High Density Polyethylene

● UV exposure for 500 hrs. via D4355 with
 ≥ 70% str. ret. (AASHTO)

OIT via D3895 ≥ 100 min.

or

OIT via D5855 \geq 400 min.

- Oven aging at 85°C via D5721 with 55% OIT remaining via D3895 or 80% OIT remaining via D5885
- Stress crack resist. via D5397-A ≥ 200 hr.

optional

(c) Polypropylene

● UV exposure for 500 hrs. via D4355 with
 ≥ 70% str. ret. (AASHTO)

OIT via D3895 ≥ ?


or

OIT via D5855 ?

Oven aging at 85°C via D5721 with ?% OIT remaining via D3895 or ?% OIT remaining via D5885 optional

Regarding Durability of the Masonry Block...


This advertisement addresses the issue, but leaves much to be desired ???




The New Paradigm


omit masonry blocks entirely
use welded wire mesh facing
either braced L-shaped or gabions
results in a green or live wall
many new variations appearing......^(*)

Welded Wire Mesh vs. Masonry Block




Welded Wire Mesh Stone Filled Gabion







Polymer Grid Stone Filled Gabion

BOMAG







Tensar's SierraScape™ Using Welded Wire L-Bracket





Seeded Erosion Control Material/Bidirectional Geogrid/Welded Wire Mesh



Beginning of Vegetative Growth



Mountain View Landfill Access Road Embankment





¢

Comments on Welded Wire Mesh Facing less costly (by a lot) ! no masonry degradation issue issue is now steel corrosion it must be evaluated – not trivial results in a green or live wall **(**) this seems to be the current direction

5.4 Maintenance by Owner and/or Designer

site visits on 6 to 12 month basis drainage patterns are critical look for stained and/or cracked blocks look for vertical settlement of backfill look for horizontal wall movement also leaning lightposts and guardrails consider monitoring: surveying, inclinometers, crack gages, and other geotech instruments if concerned

6.0 Summary and Conclusions

Summary

- SRW-wall growth is awesome
- being driven on basis of superb aesthetics and low cost
- mod. Rankine is probably too conservative
- FHWA design is sound
- NCMA also, but less conservative
- poor performance is nominal in light of the number of existing walls
- watch out for low-k backfill soils and lack of QC/QA!!!

Conclusions

- growth in SRWs with GS reinforcement is justified; providing that failures are properly analyzed and action taken to avoid in the future
- current growth shows no sign of weakening
- as technology spreads worldwide, SRWs will probably be the wall-of-choice in the future

(þ)

Thanks for Listening